PROJECT 5077 71-73 WORTH ST, BRIDGEPORT, CT


COMMUNITY DEVELOPMENT BLOCK GRANT DISASTER RECOVERY PROGRAM owner occupied rehabilityation and rebuilding CONNECTICUT DEPARTMENT OF HOUSING HARTFORD, CONNECTICUT 06112

GENERAL NOTES:

- THE CONTRACTOR SHALL ABIDE BY ALL OSHA FEDERAL STATE AND LOCAL REGULATIONS.
- THE CONTRACTOR SHALL POST ALL BONDS, PAY ALL FEES, PROVIDE PROOF OF INSURANCE AND PROVIDE TRAFFIC CONTROL NECESSARY FOR THIS WORK. REFER TO OTHER PLANS, DETAILS AND PROJECT MANUAL FOR ADDITIONAL INFORMATION. THE CONTRACTOR SHALL VERIFY ALL SITE CONDITIONS IN THE FIELD AND CONTACT MARTINEZ COUCH & ASSOCIATES IF THERE ARE ANY QUESTIONS OR CONFLICTS REGARDING THE CONSTRUCTION DOCUMENTS AND/OR FIELD CONDITIONS SO THAT APPROPRIATE REVISIONS CAN BE MADE PRIOR TO BIDDING. ANY CONFLICT BETWEEN THE DRAWINGS AND SPECIFICATIONS SHALL BE CONFIRMED WITH MARTINEZ COUCH & ASSOCIATES PRIOR TO BIDDING.
- 4. PROJECT WORK IS SUBJECT TO CONNECTICUT STATE HISTORIC PRESERVATION OFFICE WORK RESTRICTIONS
- 5. A COMMON SENSE DOCTRINE WILL APPLY. IF THE PLAN STATES THAT THE CONTRACTOR IS TO REMOVE AND REPLACE ALL SHEETROCK, AND A SECURITY SYSTEM IS ATTACHED TO THE WALL, OBVIOUSLY THE SECURITY SYSTEM IS TO BE PROTECTED TO REMAIN.

DRAWING INDEX

SHEET TITLE SHEET NUMBER TITLE SHEET T-0.0SCHEMATIC LAYOUT EXTERIOR AND ROOF A - 1.0SCHEMATIC LAYOUT FIRST FLOOR A - 1.2SCHEMATIC LAYOUT SECOND FLOOR A - 1.3SCHEMATIC LAYOUT THIRD FLOOR A - 1.4



STREET VIEW (HOUSE AT 71-73 WORTH ST, BRIDGEPORT CT)




1084 Cromwell Avenue, Suite A-2 Rocky Hill, CT 06067 Telephone: (860) 436-4364 Fax: (860) 436-4626 www.martinezcouch.com

PROJECT 5077 71-73 WORTH STREET BRIDGEPORT, CT 06604





NO.	DATE	REV	ISIONS			BY	СНК	APPV	
DRAW	N BY: MBR		CHECKED BY: REC	SCALE: N.T.S.	DATE:	04/21	/2015		

TITLE	SHEET	
JOB NO	DRAWING NUMBER	SHEET



REAR











 $\underbrace{PHOTO\ 2}_{\text{(EXISTING ROOF VALLEY REAR LEFT SIDE OF HOME)}}$



 $\frac{PHOTO \ 3}{\text{(existing roof valley rear right side of home)}}$

GENERAL NOTES

- 1. ALL DRAWINGS SHOWN ARE SCHEMATIC LAYOUTS. CONTRACTOR TO FIELD VERIFY ALL MEASUREMENTS AND CONDITIONS.
- 2. ANY DISCREPANCIES BETWEEN DRAWINGS AND CONTRACT SPECIFICATIONS AND/OR SCOPE OF WORK SHALL BE SUBMITTED IN WRITING TO MARTINEZ, COUCH, & ASSOCIATES FOR RESOLUTION.
- TO MARTINEZ, COUCH, & ASSOCIATES FOR RESOLUTION.

 3. WORK SHALL BE IN ACCORDANCE WITH ALL CONTRACT DOCUMENTS AND SPECIFICATIONS.
- 4. ANY AND ALL FINISHES, SITE FEATURES, OR OTHER PROPERTY OF THE OWNER IF DAMAGED BY THE CONTRACTOR DURING PROJECT WORK SHALL BE RESTORED OR REPLACED BY THE CONTRACTOR AT NO COST TO THE OWNER OR THE CONNECTICUT DEPARTMENT OF HOUSING.
- 5. A COMMON SENSE DOCTRINE WILL APPLY.

WORK NOTES

- DEMOLISH EXISTING ROOFING MEMBRANE AND SUBSTRATE TO RAFTERS ON ALL ROOF SLOPES. DISPOSE OF ROOFING MATERIALS PER SPECIFICATION SECTION 02 83 13, AND ASBESTOS CONTAINING MATERIALS REMOVAL PLAN, MAINTAIN FULL WEATHER PROTECTION OF THE BUILDING INTERIOR AT ALL TIMES.
- 2 DEMOLISH EXISTING BUILDING SOFFIT AND FASCIA BOARD. REBUILD PER PROJECT SPECIFICATIONS
- AREA OF FORMER CHIMNEY, CONTRACTOR SHALL FURNISH AND INSTALL NEW FRAMING AS REQUIRED FOR ROOF REPLACMENT WORK
- REMOVE AND RESET GUTTERS OR FURNISH AND INSTALL NEW 5" GUTTERS IN EXISTING LOCATIONS. MOUNT GUTTERS USING SCOTTSMAN
- 5 REMOVE AND RESET DOWNSPOUTS OR FURNISH AND INSTALL NEW 4" ROOF LEADERS IN EXISTING LOCATIONS
- FURNISH AND INSTALL 5/8" SHEATHING ICE DAM/WATER SHIELD, UNDERLAYMENT AND 30 YEAR ARCHITECTURAL SHINGLES ACCORDING TO CONTRACT SPECIFICATIONS ON ALL ROOF SLOPES
- 7 FURNISH AND INSTALL OPEN VALLEY METAL FLASHING ON MAIN ROOF VALLEY AS PER SPECIFICATIONS
- 8 REPLACE RAFTERS PER CONTRACT UNIT PRICING AND SISTER RAFTERS PER CONTACT UNIT PRICING AS NECESSARY. QUANTITIES TO BE FIELD VERIFIED BY CONTRACTOR AND MCA.

LEAD PAINT ABATEMENT GENERAL NOTES

FOR COMPREHENSIVE LEAD INSPECTION REPORT AND FULL LEAD ABATEMENT PLAN SEE CONTRACT SPECIFICATIONS. ALL LEAD ABATEMENT WORK TO BE PERFORMED IN ACCORDANCE WITH CONTRACT SPECIFICATIONS AND LEAD ABATEMENT PLAN PREPARED BY GILBERTCO LEAD INSPECTIONS LLC. CONTRACTOR SHALL COMPLY WITH ALL LOCAL, STATE, AND FEDERAL REGULATIONS APPLICABLE TO PROJECT ABATEMENT WORK AND AS INDICATED IN ABATEMENT SPECIFICATION SECTION 02 83 19.13 OF THE CONTRACT SPECIFICATIONS

ALL SURFACES SCHEDULED FOR REMOVAL OF LEADED PAINT AND LIQUID ENCAPSULATION SHALL BE REPAINTED TO MATCH ADJACENT FINISHES OR ORIGINAL COLOR AS BEST POSSIBLE COLOR MATCHING.

SURFACES SCHEDULED FOR LIQUID ENCAPSULATION SHALL BE PROPERLY STABILIZED TO ESTABLISH AN ACCEPTABLE SUBSTRATE FOR APPLICATION OF APPROVED LIQUID ENCAPSULATE MATERIAL. CONTRACTOR SHALL PERFORM X—TEST ON REPRESENTATIVE SURFACE AND SAMPLE AREAS.

ALL DEMOLITION MATERIALS ASSOCIATED WITH LEAD ABATEMENT WORK SHALL BE DISPOSED PER THE LEAD ABATEMENT PLAN AS HAZARDOUS WASTE WITH A TCLP READING GREATER THAN 5 mG/L. ALL LICENSES, TESTING RESULTS, AND MANIFESTS MUST BE SUBMITTED PER THE CONTRACT DOCUMENTS.

ASBESTOS CONTAINING MATERIALS GENERAL NOTES

ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH 'ASBESTOS CONTAINING MATERIALS REMOVAL WORK PLAN, 71-73 WORTH STREET, BRIDGEPORT, CT' PREPARED BY FACILITY SUPPORT SERVICES LLC. CONTRACTOR SHALL COMPLY WITH ALL LOCAL, STATE, AND FEDERAL REGULATIONS APPLICABLE TO PROJECT ABATEMENT WORK.

SUSPECT MATERIALS — ROOFING SHINGLES HAVE BEEN TESTED AND HAVE BEEN FOUND TO BE NON ACM. ALL OTHER MATERIALS INCLUDING BUT NOT LIMITED TO TARS AND SEALANTS ARE ASSUMED AS ACM AND ARE TO BE TREATED AS SUCH. MATERIALS MAY ALSO CONTAIN POLYCHLORINATED BIPHENYLS (PCB'S). THE TESTING OF SUSPECT ROOF MATERIALS FOR DISPOSAL CHARACTERIZATION IS THE RESPONSIBILITY OF THE CONTRACTOR.

CONTRACTOR LICENSING — THE ROOFING DEMOLITION WORK SHALL BE PERFORMED BY AN ASBESTOS ABATEMENT CONTRACTOR LICENSED IN THE STATE OF CONNECTICUT. WORKERS SHALL BE TRAINED IN ACCORDANCE WITH 29 CFR 1910.120 FOR THE REMOVAL AND HANDLING OF POLYCHLORINATED BIPHENYLS (PCB'S).

THE ACM REMOVAL WORK PLAN IS DESCRIBED IN NARRATIVE FORM AS FOLLOWS FOR CONTRACTORS INFORMATION PURPOSES. SPECIFIC PHASING AND WORK REQUIREMENTS SHALL CONFORM AS NOTED ABOVE.

- 1. <u>PRECONSTRUCTION MEETING</u> PRIOR TO ROOF DEMOLITION WORK THE CONTRACTOR, MCA AND OTHER NECESSARY PERSONNEL SHALL ATTEND A PRECONSTRUCTION MEETING TO REVIEW THE DEMOLITION SCHEDULE AND ACM REMOVAL WORK PLAN.
- 2. REMOVAL PROCEDURES PRIOR TO WORK START A REGULATED AREA AND PROTECTION TO RESTRICT ACCESS TO REGULATED PERSONNEL ONLY SHALL BE ESTABLISHED. MATERIALS ARE TO BE REMOVED IN A MANNER THAT DOES NOT GENERATE VISIBLE EMISSIONS AND MAINTAINS THE ROOFING MATERIALS IN A NON-FRIABLE CONDITION. IF THE MATERIAL BECOMES FRIABLE AS DETERMINED BY MCA'S OR THE CONTRACTORS LICENSED ASEBESTOS PROJECT MONITOR WORK SHALL CEASE AND ALL MATERIAL SHALL BE HANDLED AS REGULATED ASBESTOS WASTE.
- 3. <u>DISPOSAL</u> PRIOR TO DISPOSAL REPRESENTATIVE ROOFING MATERIALS SHALL BE TESTED BY A STATE OF CONNECTICUT CERTIFIED LABORATORY VIA SOXHLET EXTRACTION METHOD FOR THE PURPOSE OF DISPOSAL CHARACTERIZATION. REPRESENTATIVE MATERIAL TYPES SHALL BE DETERMINED JOINTLY BY THE CONTRACTOR AND MCA AND IT'S REPRESENTATIVES JOINTLY.

MARTINEZ COUCH & ASSOCIATES
ENGINEERING • LAND SURVEYING • ENVIRONMENTAL

1084 Cromwell Avenue, Suite A-2 Rocky Hill, CT 06067 Telephone: (860) 436-4364 Fax: (860) 436-4626 www.martinezcouch.com

SCALE 1" = 5'

PROJECT 5077 71-73 WORTH STREET BRIDGEPORT, CT 06604 ISSUED FOR BID NOT FOR CONSTRUCTION


NO. DATE REVISIONS						BY	СНК	APPV
DRAWN BY: MBR			CHECKED BY: REC	SCALE: AS NOTED	DATE:	04/21	/2015	

SCHEMATIC LAYOUT

EXTERIOR AND ROOF

JOB NO.	DRAWING NUMBER	SHEET
33-262-5077	BASEMAP 33-262-5077.dwg	A-1.0

REAR



INTERIOR	1ST FLOOR PAINT	ING SCHEDULE	
PRIMER COAT INTERMEDIATE COAT		TOP COAT	
REAR EXTERIOR DOOR/INTERIOR FACE	LATEX PRIMER	LATEX FLAT	LATEX FLAT
INTERIOR TRIM/CASING AT REAR DOOR	LATEX PRIMER	LATEX LOW SHEEN	LATEX LOW SHEEN
BATHROOM CEILING/WALL	LATEX PRIMER	LATEX FLAT	LATEX FLAT
HALL OUTSIDE CEILING/WALL	LATEX PRIMER	LATEX FLAT	LATEX FLAT
KITCHEN WALLS	LEAD BARRIER COMPOUND	LATEX FLAT	LATEX FLAT
KITCHEN WALL #2 DOOR JAMB/CASING PORTAL TO HALL	LEAD BARRIER COMPOUND	LATEX LOW SHEEN	LATEX LOW SHEEN
KITCHEN WALL #3 DOOR CASING DOOR TO REAR HALL AND PANTRY	LEAD BARRIER COMPOUND	LATEX LOW SHEEN	LATEX LOW SHEEN
KITCHEN WALL #4 WINDOW STOOL/CHAIR RAIL TRIM	LEAD BARRIER COMPOUND	LATEX LOW SHEEN	LATEX LOW SHEEN

EXTERIOR	1ST FLOOR PAINT	TING SCHEDULE	
	PRIMER COAT	INTERMEDIATE COAT	TOP COAT
REAR DOOR EXTERIOR CASING/TRIM	LATEX PRIMER	LATEX LOW SHEEN	LATEX LOW SHEEN
REAR PORCH RAIL/BALLUSTER	LATEX PRIMER	LATEX LOW SHEEN	LATEX LOW SHEEN
REAR PORCH FLOOR/STAIRS	LEAD BARRIER COMPOUND	LATEX LOW SHEEN	LATEX LOW SHEEN
REAR PORCH COLUMNS/CEILING/DECORATIVE TRIM	LEAD BARRIER COMPOUND	LATEX LOW SHEEN	LATEX LOW SHEEN
FRONT DOOR CASING (TWO FRONT DOORS)	LEAD BARRIER COMPOUND	LATEX LOW SHEEN	LATEX LOW SHEEN
FRONT DOOR THRESHOLD (TWO FRONT DOORS)	LEAD BARRIER COMPOUND	LATEX LOW SHEEN	LATEX LOW SHEEN
FRONT PORCH LATTICE*	LEAD BARRIER COMPOUND	LATEX LOW SHOWN	LATEX LOW SHEEN
FRONT PORCH COLUMNS/CEILING/ DECORATIVE TRIM/RAILINGS/BALLUSTERS	LEAD BARRIER COMPOUND	LATEX LOW SHEEN	LATEX LOW SHEEN

* IF REPLACING FRONT LATTICE USE LATEX PRIMER AND 2 COATS OF LATEX FLAT PAINT



PHOTO 1

(WATER DAMAGED GYPSUM BOARD CEILING)



PHOTO 2
(HALL OUTSIDE BATHROOM)




PHOTO 3

(WATER DAMAGED GYPSUM BOARD IN BATHROOM)



PHOTO 3

(KITCHEN WINDOW COMPONENTS TYPICAL)

GENERAL NOTES

- ALL DRAWINGS SHOWN ARE SCHEMATIC LAYOUTS. CONTRACTOR TO FIELD VERIFY ALL MEASUREMENTS AND CONDITIONS.
- 2. ANY DISCREPANCIES BETWEEN DRAWINGS AND CONTRACT SPECIFICATIONS

 AND/OR SCOPE OF WORK SHALL BE SUBMITTED IN WRITING TO
- MARTINEZ, COUCH, & ASSOCIATES FOR RESOLUTION.

 3. WORK SHALL BE IN ACCORDANCE WITH ALL CONTRACT DOCUMENTS AND SPECIFICATIONS.
- 4. ANY AND ALL FINISHES, SITE FEATURES, OR OTHER PROPERTY OF THE OWNER IF DAMAGED BY THE CONTRACTOR DURING PROJECT WORK SHALL BE RESTORED OR REPLACED BY THE CONTRACTOR AT NO COST TO THE OWNER OR THE CONNECTICUT DEPARTMENT OF HOUSING.
- 5. A COMMON SENSE DOCTRINE WILL APPLY.

LEAD PAINT ABATEMENT GENERAL NOTES

FOR COMPREHENSIVE LEAD INSPECTION REPORT AND FULL LEAD ABATEMENT PLAN SEE CONTRACT SPECIFICATIONS. ALL LEAD ABATEMENT WORK TO BE PERFORMED IN ACCORDANCE WITH CONTRACT SPECIFICATIONS AND LEAD ABATEMENT PLAN PREPARED BY GILBERTCO LEAD INSPECTIONS LLC. CONTRACTOR SHALL COMPLY WITH ALL LOCAL, STATE, AND FEDERAL REGULATIONS APPLICABLE TO PROJECT ABATEMENT WORK AND AS INDICATED IN ABATEMENT SPECIFICATION SECTION 02 83 19.13 OF THE CONTRACT SPECIFICATIONS


ALL SURFACES SCHEDULED FOR REMOVAL OF LEADED PAINT AND LIQUID ENCAPSULATION SHALL BE REPAINTED TO MATCH ADJACENT FINISHES OR ORIGINAL COLOR AS BEST POSSIBLE COLOR MATCHING.

SURFACES SCHEDULED FOR LIQUID ENCAPSULATION SHALL BE PROPERLY STABILIZED TO ESTABLISH AN ACCEPTABLE SUBSTRATE FOR APPLICATION OF APPROVED LIQUID ENCAPSULATE MATERIAL. CONTRACTOR SHALL PERFORM X—TEST ON REPRESENTATIVE SURFACE AND SAMPLE AREAS

ALL DEMOLITION MATERIALS ASSOCIATED WITH LEAD ABATEMENT WORK SHALL BE DISPOSED PER THE LEAD ABATEMENT PLAN AS HAZARDOUS WASTE WITH A TCLP READING GREATER THAN 5 mG/L.

- WOOD WINDOW TO BE REPLACED WITH ALL WOOD WINDOW REPLACEMENT FOR LEAD ABATEMENT. REMOVE AND REPLACE ALL STORM WINDOWS AND SCREENS AS REQUIRED TO COMPLETE WINDOW REPLACEMENT.
- FURNISH AND INSTALL NEW SOLD WOOD DOOR FOR LEAD PAINT ABATEMENT.
 REPLACE ALL DOOR FRAMING COMPONENTS. INCLUDING CASING, DOOR SLAB AND JAMBS.
- 3 LIQUID ENCAPSULATE KITCHEN WALLS WITH CONNECTICUT DEPARTMENT OF PUBLIC HEALTH APPROVED ENCAPSULANT
- 4 LIQUID ENCAPSULATE PANTRY DOOR CASING WITH CONNECTICUT DEPARTMENT OF PUBLIC HEALTH APPROVED ENCAPSULANT
- LIQUID ENCAPSULATE INTERIOR WINDOW TRIM AND STOOL WITH CONNECTICUT DEPARTMENT OF PUBLIC HEALTH APPROVED ENCAPSULANT
- 6 LIQUID ENCAPSULATE DOORWAY JAMB AND CASINGS WITH CONNECTICUT DEPARTMENT OF PUBLIC HEALTH APPROVED ENCAPSULANT
- 7 LIQUID ENCAPSULATE DOORWAY CASINGS WITH CONNECTICUT DEPARTMENT OF PUBLIC HEALTH APPROVED ENCAPSULANT
- NON-INTACT LEADED SURFACE ON CEILING AND WALLS OF BATHROOM
 HALLWAY. DEMOLISH AND DISPOSE OF CEILING AND WALLS AND CEILING AS
 LEADED WASTE PER LEAD ABETMENT SPECIFICATION. FURNISH AND INSTALL
 NEW GYPSUM WALL BOARD. TAPE, PRIME, AND PAINT TO MATCH EXISTING
- DEMOLISH ALL CEILING GYPSUM BOARD AND WALL GYPSUM BOARD IN BATHROOM. APPLY ANTI-MICROBIAL TREATMENT. FURNISH AND INSTALL GYPSUM BOARD WHERE REMOVED. TAPE AND PAINT TO MATCH ADJACENT
- FINISHES.

 SALVAGE SPINDLES ON 1ST FLOOR PORCH FOR REUSE ON THE FIRST FLOOR
 AND SECOND FLOOR FRONT PORCHS. CONTRACTOR SHALL PROTECT SPINDLES
- AND REPLACE LOST, STOLEN, DAMAGED, OR OTHERWISE MISSING SPINDLES WITH CUSTOM MILLED SPINDLES OF IDENTICAL MATERIAL AND PROFILE FOR INSTALLATION ON FRONT PORCH. FURNISH AND INSTALL NEW WOODEN RAILINGS AND BALLUSTERS ON REAR FIRST FLOOR FRONT PORCH, PRIME AND PAINT.
- STABILIZE AND LIQUID ENCAPSULATE ALL SURFACES ON REAR PORCH EXCEPT FLOOR AND NEW RAILINGS.
- REMOVE AND DISPOSE OF PAINT ON FRONT AND REAR PORCH FLOORING.
 LIQUID ENCAPSULATE AND PAINT WITH EXTERIOR FLOOR PAINT.
- STABILIZE AND LIQUID ENCAPSULATE LATTICE UNDER PORCH, COLUMNS, RAILINGS, BALUSTERS, CEILINGS AND DOOR CASINGS.
- REMOVE PAINT ON DOOR THRESHOLDS. AT FRONT ENTRANCE DOORS LIQUID ENCAPSULATE AND RE-PAINT.



WORTH STREET

FIRST FLOOR LAYOUT

SCALE 1" = 5'

PROJECT 5077 71-73 WORTH STREET BRIDGEPORT, CT 06604



NO.	DATE	REV	/ISIONS			BY	СНК	APPV
DRAV	VN BY: MBR		CHECKED BY: REC	SCALE: AS NOTED	DATE:	04/21	/2015)

SCHEMATIC LAYOUT

FIRST FLOOR


JOB NO. DRAWING NUMBER SHEET

33-262-5077 BASEMAP 33-262-5077.dwg A-1.1

1084 Cromwell Avenue, Suite A-2
Rocky Hill, CT 06067
Telephone: (860) 436-4364
Fax: (860) 436-4626

Www.martinezcouch.com

CONSTRUCTION INSPECTION • GIS • WASTEWATER



INTERIOR	2ND FLOOR PAINT	ING SCHEDULE	
	PRIMER COAT	INTERMEDIATE COAT	TOP COAT
REAR EXTERIOR DOOR	LATEX	LATEX, FLAT	LATEX, FLAT
INTERIOR TRIM/CASING AT REAR DOOR	LATEX	LATEX, LOW SHEEN	LATEX, LOW SHEEN
BEDROOM CEILING	LATEX	LATEX, FLAT	LATEX, FLAT

EXTERIOR	2ND FLOOR PAIN	TING SCHEDULE	
	PRIMER COAT	INTERMEDIATE COAT	TOP COAT
REAR EXTERIOR DOOR	LATEX	LATEX, FLAT	LATEX, FLAT
REAR EXTERIOR DOOR CASING/TRIM	LATEX	LATEX, LOW SHEEN	LATEX, LOW SHEEN
REAR PORCH RAIL/BALLUSTER	LATEX	LATEX, LOW SHEEN	LATEX, LOW SHEEN
REAR PORCH FLOOR/STAIRS	LEAD BARRIER COMPOUND	LATEX, LOW SHEEN	LATEX, LOW SHEEN
REAR PORCH COLUMNS/CEILING/DECORATIVE TRIM	LEAD BARRIER COMPOUND	LATEX, LOW SHEEN	LATEX, LOW SHEEN
FRONT DOOR CASING	LEAD BARRIER COMPOUND	LATEX, LOW SHEEN	LATEX, LOW SHEEN
FRONT DOOR THRESHOLD	LEAD BARRIER COMPOUND	LATEX, LOW SHEEN	LATEX, LOW SHEEN
FRONT PORCH COLUMNS/CEILING/ DECORATIVE TRIM/RAILINGS/BALLUSTERS	LEAD BARRIER COMPOUND	LATEX, LOW SHEEN	LATEX, LOW SHEEN



PHOTO 1 (2ND FLOOR PORCH EXISTING CONDITIONS)




PHOTO 1 (REAR OF HOME)



PHOTO 3 (WATER DAMAGED PLASTER CEILING FOR REPAIR)

GENERAL NOTES

- 1. ALL DRAWINGS SHOWN ARE SCHEMATIC LAYOUTS. CONTRACTOR TO FIELD VERIFY ALL MEASUREMENTS AND CONDITIONS.
- 2. ANY DISCREPANCIES BETWEEN DRAWINGS AND CONTRACT SPECIFICATIONS
- AND/OR SCOPE OF WORK SHALL BE SUBMITTED IN WRITING TO MARTINEZ, COUCH, & ASSOCIATES FOR RESOLUTION.
- 3. WORK SHALL BE IN ACCORDANCE WITH ALL CONTRACT DOCUMENTS AND SPECIFICATIONS.
- ANY AND ALL FINISHES, SITE FEATURES, OR OTHER PROPERTY OF THE OWNER IF DAMAGED BY THE CONTRACTOR DURING PROJECT WORK SHALL BE RESTORED OR REPLACED BY THE CONTRACTOR AT NO COST TO THE OWNER OR THE CONNECTICUT DEPARTMENT OF HOUSING.
- 5. A COMMON SENSE DOCTRINE WILL APPLY.

LEAD PAINT ABATEMENT GENERAL NOTES

FOR COMPREHENSIVE LEAD INSPECTION REPORT AND FULL LEAD ABATEMENT PLAN SEE CONTRACT SPECIFICATIONS. ALL LEAD ABATEMENT WORK TO BE PERFORMED IN ACCORDANCE WITH CONTRACT SPECIFICATIONS AND LEAD ABATEMENT PLAN PREPARED BY GILBERTCO LEAD INSPECTIONS LLC. CONTRACTOR SHALL COMPLY WITH ALL LOCAL, STATE, AND FEDERAL REGULATIONS APPLICABLE TO PROJECT ABATEMENT WORK AND AS INDICATED IN ABATEMENT SPECIFICATION SECTION 02 83 19.13 OF THE CONTRACT SPECIFICATIONS

ALL SURFACES SCHEDULED FOR REMOVAL OF LEADED PAINT SHALL BE REPAINTED TO MATCH ADJACENT FINISHES OR ORIGINAL COLOR AS BEST POSSIBLE COLOR

SURFACES SCHEDULED FOR LIQUID ENCAPSULATION SHALL BE PROPERLY STABILIZED TO ESTABLISH AN ACCEPTABLE SUBSTRATE FOR APPLICATION OF APPROVED LIQUID ENCAPSULANT MATERIAL.

ALL DEMOLITION MATERIALS ASSOCIATED WITH LEAD ABATEMENT WORK SHALL BE DISPOSED PER THE LEAD ABATEMENT PLAN AS HAZARDOUS WASTE WITH A TCLP READING GREATER THAN 5 mG/L.

- WOOD WINDOW TO BE REPLACED WITH ALL WOOD WINDOW REPLACEMENT FOR LEAD ABATEMENT. REMOVE AND REPLACE ALL STORM WINDOWS AND SCREENS AS REQUIRED TO COMPLETE WINDOW REPLACEMENT.
- FURNISH AND INSTALL NEW SOLD WOOD DOOR FOR LEAD PAINT ABATEMENT. REPLACE ALL DOOR FRAMING COMPONENTS. INCLUDING CASING, DOOR SLAB
- REMOVE AND DISPOSE OF RAILINGS ON REAR SECOND FLOOR PORCH. FURNISH AND INSTALL NEW HAND RAILS AND BALLUSTERS ON REAR FIRST FLOOR PORCH TO MATCH PROFILE INSTALLED ON REAR FIRST FLOOR PORCH.
- STABILIZE AND LIQUID ENCAPSULATE ALL PORCH RAILINGS, COLUMNS, DECORATIVE TRIM AND WOOD MOLDING WITH CT DEPARTMENT OF PUBLIC HEALTH APPROVED LIQUID ENCAPSULANT
- SALVAGE SPINDLES ON REAR 1ST FLOOR PORCH FOR REUSE ON THE FIRST AND SECOND FLOOR FRONT PORCH. CONTRACTOR SHALL PROTECT SPINDLES AND REPLACE LOST, STOLEN, DAMAGE, OR OTHERWISE MISSING SPINDLES WITH CUSTOM MILLED SPINDLES OF IDENTICAL MATERIAL AND PROFILE FOR INSTALLATION ON FRONT PORCH.
 - STABILIZE AND LIQUID ENCAPSULATE ALL PORCH RAILINGS, COLUMNS, DECTORATIVE TRIM AND WOOD MOLDING ON SECOND FLOOR FRONT PORCH WITH CT DEPARTMENT OF PUBLIC HEALTH APPROVED LIQUID ENCAPSULANT.
- PATCH REPAIR WATER DAMAGE PLASTER CEILILNG IN FRONT LEFT BEDROOM. PRIME AND PAINT ENTIRE CEILING.

MARTINEZ COUCH & ASSOCIATES ENGINEERING • LAND SURVEYING • ENVIRONMENTAL

1084 Cromwell Avenue, Suite A-2 Rocky Hill, CT 06067 Telephone: (860) 436-4364 Fax: (860) 436-4626 www.martinezcouch.com

WORTH STREET

SECOND FLOOR LAYOUT

SCALE 1" = 5


PROJECT 5077 71-73 WORTH STREET BRIDGEPORT, CT 06604 ISSUED FOR BID NOT FOR CONSTRUCTION

NO. DATE REVISIONS					BY	СНК	APPV		
DRAWN BY: MBR			CHECKED BY: REC	5	SCALE: AS NOTED	DATE:	04/2	1/2015	,

SCHEMATIC LAYOUT

SECOND FLOOR

DRAWING NUMBER SHEET 33-262-5077 BASEMAP 33-262-5077.dwg A-1.2 REAR



FRONT

WORTH STREET

THIRD FLOOR LAYOUT SCALE 1" = 5'






PHOTO 1 (WOOD WINDOW FOR REPLACEMENT AS PART OF LEAD PAINT ABATEMENT, TYPICAL)




PHOTO 2 (WOOD WINDOW FOR REPLACEMENT AS PART OF LEAD PAINT ABATEMENT, TYPICAL)

GENERAL NOTES

- 1. ALL DRAWINGS SHOWN ARE SCHEMATIC LAYOUTS. CONTRACTOR TO FIELD VERIFY ALL MEASUREMENTS AND CONDITIONS.
- 2. ANY DISCREPANCIES BETWEEN DRAWINGS AND CONTRACT SPECIFICATIONS AND/OR SCOPE OF WORK SHALL BE SUBMITTED IN WRITING TO
- MARTINEZ, COUCH, & ASSOCIATES FOR RESOLUTION. 3. WORK SHALL BE IN ACCORDANCE WITH ALL CONTRACT DOCUMENTS AND SPECIFICATIONS.
- 4. ANY AND ALL FINISHES, SITE FEATURES, OR OTHER PROPERTY OF THE OWNER IF DAMAGED BY THE CONTRACTOR DURING PROJECT WORK SHALL BE RESTORED OR REPLACED BY THE CONTRACTOR AT NO COST TO THE OWNER OR THE CONNECTICUT DEPARTMENT OF HOUSING
- 5. A COMMON SENSE DOCTRINE WILL APPLY.

LEAD PAINT ABATEMENT

GENERAL NOTES

FOR COMPREHENSIVE LEAD INSPECTION REPORT AND FULL LEAD ABATEMENT PLAN SEE CONTRACT SPECIFICATIONS. ALL LEAD ABATEMENT WORK TO BE PERFORMED IN ACCORDANCE WITH CONTRACT SPECIFICATIONS AND LEAD ABATEMENT PLAN PREPARED BY GILBERTCO LEAD INSPECTIONS LLC. CONTRACTOR SHALL COMPLY WITH ALL LOCAL, STATE, AND FEDERAL REGULATIONS APPLICABLE TO PROJECT ABATEMENT WORK AND AS INDICATED IN ABATEMENT SPECIFICATION SECTION 02 83 19.13 OF THE CONTRACT SPECIFICATIONS


ALL SURFACES SCHEDULED FOR REMOVAL OF LEADED PAINT SHALL BE REPAINTED TO MATCH ADJACENT FINISHES OR ORIGINAL COLOR AS BEST POSSIBLE COLOR MATCHING.

SURFACES SCHEDULED FOR LIQUID ENCAPSULATION SHALL BE PROPERLY STABILIZED TO ESTABLISH AN ACCEPTABLE SUBSTRATE FOR APPLICATION OF APPROVED LIQUID ENCAPSULANT MATERIAL.

ALL DEMOLITION MATERIALS ASSOCIATED WITH LEAD ABATEMENT WORK SHALL BE DISPOSED PER THE LEAD ABATEMENT PLAN AS HAZARDOUS WASTE WITH A TCLP READING GREATER THAN 5 mG/L.









1084 Cromwell Avenue, Suite A-2 Rocky Hill, CT 06067 Telephone: (860) 436-4364 Fax: (860) 436-4626

PROJECT 5077 71-73 WORTH STREET BRIDGEPORT, CT 06604



NO.	DATE	REVISIONS		BY	СНК	APPV

SCHEMATIC LAYOUT

THIRD FLOOR

DRAWING NUMBER 33-262-5077 BASEMAP 33-262-5077.dwg A-1.3